81

No.	Items of work	Per	Ground floor	Upper floor	Lock-up and compound	Miscellaneous	Total
			Quantity	Quantity	Quantity	Quantity	Quantity
19	Reinforced concrete pillars with bases and capitals complete	C. ft.	...	...	27	...	27
20	Do do	,,	...	63	...	...	63
21	Teak wood doors ¾th panelled both sides and ¼th glazed with glass fanlight above including hinges, bolts, locks and iron hold fasts etc., complete	S. ft.	278	...	...	...	278
22	Do do without fanlight	,,	...	160	...	...	160
23	Teak wood windows outside panelled, inside glazed fanlights above with iron bars etc, complete	,,	485	...	...	...	485
24	Do do	,,	...	96	...	...	96
25	Do do without fanlights	,,	...	289	...	...	289
26	Teak wood glazed ventilators	,,	...	74	...	...	74
27	Teak wood doors with iron barred shutters including painting	,,	...	...	72	...	72
28	Teak wood batten window with iron bars including painting	,,	...	...	10	...	10
29	Teak wood ventilators with iron bars and perforated zinc sheet including painting	,,	...	...	38	...	38
30	Painting doors and windows	Sqr.	17·61	...	...	...	17·61
31	Do do	,,	...	15·10	...	...	15·10
32	Parapet wall with pillasters and etc., complete 2½' height and ¾' thick	R. ft.	...	150	..	...	150
33	Parapet wall with pillasters and etc., complete 1½' hight and ¾' thick	,,	...	169	...	...	169
34	Do do do	,,	...	..	218	...	218
35	Cornice walls alround the building 1½ feet deep	,,	221	...		...	221
36	Do do	,,	...	315	..	...	315
37	Do 9" deep	,,	...	...	198	...	198
38	String course or light cornice	,,	173	...	...	...	173
39	Do do	,,	...	66	...	...	66
40	Flooring with Cudapah slabs over 3" concrete and cement pointing	Sqr.	18·17	..	9·78	..	27·95
41	Cast iron railings	R. ft.	...	63	...	...	63
42	Teak wood stair case with ornamental cast iron railings	No.	1	...	...	...	1
43	Armouring girders with concrete	L. S.	L. S.	L. S.	L. S.	...	...
44	Coping with brick in chunnam including plastering	R. ft.	...	...	55	...	55
45	Gravelling the open yard between main building and Lock up	C. yds.	...	...	26	...	26
46	Down pipes	L. S.	...	L. S.	L. S.	...	...
47	Drains alround the building	R. ft.	...	...	..	320	320
48	Clearing site after dismantling the old building, levelling ground and forming approach roads etc., complete	L. S.	...	...	...	L. S.	...
49	Compound wall with gate pillars and gate etc., complete (two sides and rear)	,,	...	...	...	L. S.	...
50	Constructing latrines	,,	...	...	...	,,	...

B. S. VENKATACHAR,
Executive Engineer.

KADUR DIVISION.

Notice.

The attention of the public is invited to the notification in this *Gazette*, dated 9th July 1908, calling for tenders for Improving the Ramanahalli Channel, in Chikmagalur Taluk.

R S. NAVARATHNA,
Exec. Engineer.

2 K